

FUL.-S. DEFIANCE ST. (SR 66)-1.95 RESURFACING
CONTRACT 1-10 (PID 86319)

This project consists of curb replacement and resurfacing of South Defiance Street from Barre Road to the railroad right-of-way. South Defiance Street will have most of its existing asphalt pavement ground down approximately 2-1/4 inches. From 200 feet north of Oak and Wilson Streets to Beech Street, South Defiance Street will be raised 1 inch to 4 inches higher than the existing pavement. The entire street will be resurfaced with two asphalt courses. The new pavement is to be paint striped similar to the existing paint scheme.

New concrete driveway approaches will be constructed from the curb to the existing sidewalk for most of the houses and businesses. Some driveways will have their concrete replaced far enough back to allow for the new curbs to be installed. The new concrete driveway approached in the raised section of South Defiance Street will have flatter slopes than the steep slopes that are presently exist.

New ADA compliant concrete sidewalk ramps are to be installed within the project limits. The new ramps will have cast iron truncated dome panels installed and flatter slopes constructed where necessary.