

NOLAN PARKWAY IMPROVEMENTS PHASE III
CONTRACT 3-09

The primary objective of this project is to extend Nolan Parkway approximately 3,000 feet from the existing end of the street in the Archbold Industrial Park to Township Road 24. The majority of the proposed roadway will consist of two, twelve (12) foot wide asphalt travel lanes. Concrete curb and gutter on both sides of the street will give a total street width of twenty-nine (29) feet from back of curb to back of curb. Where Nolan Parkway intersects Township Road 24, a designated left and right turn lane will be constructed.

Storm sewers necessary to drain the proposed roadway and surrounding areas will be constructed along the entire length of the project. The majority of the storm sewers will outlet into the Archbold Industrial Park storm sewer system. However, about 300 feet of the west-most portion of the proposed roadway drainage will outlet to existing drainage on Township Road 24.

A twelve (12) inch waterline that will provide fire protection will be extended west along the north side of the proposed street. A twelve (12) inch sanitary sewer will be extended west along the south side of the street. Both the waterline and the sanitary sewer will stop short of reaching Township Road 24 by 1200 feet.

Two concrete approaches will be constructed. One approach will allow access for an adjacent landowner, while the other approach will permit access to stone and topsoil stockpiles on Village property in the Industrial Park. The entire existing portion of Nolan Parkway will be milled one and one half (1-1/2) inches deep and resurfaced with modified asphalt. The project will also consist of pavement striping along the entire length of the existing and proposed Nolan Parkway.